

- A. Sand placement from beach nourishment, sand bypass, and sand back pass activities;
- B. Sand placement from navigation channel maintenance; and
- C. Groin and jetty repair or replacement.

If the Corps is unable to comply with the Reasonable and Prudent Measures and Terms and Conditions, the Corps as the construction agent or regulatory authority may:

1. Inform the Service why the term and condition is not reasonable and prudent for the specific project or activity and request exception under the SPBO or
2. Initiate consultation with the Service for the specific project or activity. The Service may respond by either of the following:
 - a. Allowing an exception to the terms and conditions under the SPBO or
 - b. Recommending or accepting initiation of consultation (if initiated by the Corps) for the specific project or activity.

Post construction requirements are listed in Reasonable and Prudent measures A10, A11, A12, and A13. These post construction requirements are subject to congressional authorization and the allocation of funds. If the Corps or Applicant cannot fulfill these Reasonable and Prudent Measures, the Corps must reinitiate consultation.

REASONABLE AND PRUDENT MEASURES for:

A. Projects that include sand placement from beach nourishment, sand bypass, and sand back pass activities primarily for shore protection shall include the following measures:

- A1. Conservation Measures included in the Corps' PBA that address protection of nesting sea turtles and beach mice shall be implemented in the Corps federally authorized project or regulated activity.
- A2. Beach quality sand suitable for sea turtle nesting, successful incubation, and hatchling emergence and beach mouse burrow construction shall be used for sand placement.
- A3. Sand placement shall not occur during the period of peak sea turtle egg laying and egg hatching, to reduce the possibility of sea turtle nest burial, crushing of eggs, or nest excavation. In Brevard, Indian River, St. Lucie, Martin, Palm Beach, and Broward counties, sand placement shall not occur from May 1 through October 31. In St. Joseph Peninsula State Park, St. Joseph peninsula, and Cape San Blas in Gulf County, St. George Island in Franklin County, and Manasota Key in Sarasota and Charlotte counties, sand placement shall not occur from June 1 through September 30. In Nassau, Duval, St. Johns, Flagler, Volusia, Miami-Dade, Monroe, Collier, Lee, Charlotte (except Manasota Key), Sarasota (except Manasota Key), Manatee, Hillsborough, Pinellas, Franklin (except St. George Island), Gulf (except St. Joseph Peninsula State Park, St. Joseph peninsula, and Cape San Blas), Bay, Walton, Okaloosa, Santa Rosa, and Escambia counties, Florida, sand placement may occur during the sea turtle nesting season.

- A4. All derelict material or other debris shall be removed from the beach prior to any sand placement.
- A5. The Corps shall continue to work with FDEP, FWC and the Service to create a sea turtle friendly beach profile for placement of material during construction.
- A6. If a dune system is already part of the project design, the placement and design of the dune shall emulate the natural dune system to the maximum extent possible, including the dune configuration and shape.
- A7. Predator-proof trash receptacles shall be installed and maintained at all beach access points used for the project construction to minimize the potential for attracting predators of sea turtles and beach mice.
- A8. A meeting between representatives of the Applicant's or Corps, Service, FWC, the permitted sea turtle surveyor, and other species surveyors, as appropriate, shall be held prior to the commencement of work on this project.
- A9. If the beach nourishment project will be conducted during the sea turtle nesting season, surveys for nesting sea turtles must be conducted. Surveys for early and late nesting sea turtles shall be conducted where appropriate. If nests are constructed in the area of sand placement, the eggs shall be relocated to minimize sea turtle nest burial, crushing of eggs, or nest excavation.
- A10. A post construction survey(s) of all artificial lighting visible from the project beach shall be completed by the Applicant or Corps.
- A11. Daily nesting surveys shall be conducted by the Applicant or Corps for two nesting seasons following construction if the new sand still remains on the beach.
- A12. Sand compaction shall be monitored and tilling shall be conducted if needed to reduce the likelihood of impacting sea turtle nesting and hatching activities.
- A13. Escarpment formation shall be monitored and leveling shall be conducted if needed to reduce the likelihood of impacting nesting and hatchling sea turtles.
- A14. Construction equipment and materials shall be stored in a manner that will minimize impacts to nesting and hatchling sea turtles and beach mice.
- A15. Lighting associated with the project construction shall be minimized to reduce the possibility of disrupting and disorienting nesting and hatchling sea turtles and nocturnal activities of beach mice.
- A16. During the sea turtle nesting season, the Corps shall not extend the beach fill more than 500 feet (or other agreed upon length) between dusk and the time of completion the following day's nesting survey to reduce the impact to emerging sea turtles and burial of new nests.

- A17. All vegetation planting shall be designed and conducted to minimize impacts to sea turtles and beach mice.
- A18. Beach mouse habitat shall be avoided when selecting sites for storage and staging of equipment to the maximum extent possible.
- A19. Equipment and construction materials shall not be stored near the seaward dune toe in areas of occupied beach mouse habitat. This area is highly utilized by beach mice.
- A20. Existing vegetated habitat at beach access points and travel corridors shall be protected to the maximum extent possible to ensure vehicles and equipment transport stay within the access corridor.
- A21. Expanded or newly created beach access points shall be restored following construction.
- A22. A report describing the actions taken shall be submitted to the Service following completion of the proposed work for each year when the activity has occurred.
- A23. The Service and the FWC shall be notified if a sea turtle adult, hatchling, or egg, or beach mouse is harmed or destroyed as a direct or indirect result of the project.

TERMS AND CONDITIONS

All conservation measures described in the Corps' PBA are hereby incorporated by reference as Terms and Conditions within this document pursuant to 50 CFR §402.14(I) with the addition of the following Terms and Conditions. In order to be exempt from the prohibitions of section 9 of the Act, the Corps shall comply with the following Terms and Conditions, which implement the Reasonable and Prudent Measures, described above and outline required reporting/monitoring requirements.

These Terms and Conditions are nondiscretionary.

Post construction requirements are listed in Terms and Conditions A10, A11, A12, and A13. These post construction requirements are subject to congressional authorization and the allocation of funds. If the Corps or Applicant cannot fulfill these Terms and Conditions, the Corps must reinitiate consultation.

TERMS AND CONDITIONS for:

A. Projects that include sand placement from beach nourishment, sand bypass, and sand back pass activities primarily for shore protection shall include the following conditions:

All beaches

- A1. Conservation Measures included in the Corps' PBA that address protection of nesting sea turtles and beach mice listed on pages 9 and 10 of the SPBO shall be implemented in the Corps federally authorized project or regulated activity.

- A2. Beach compatible fill shall be placed on the beach or in any associated dune system. Beach compatible fill must be sand that is similar to a native beach in the vicinity of the site that has not been affected by prior sand placement activity. The fill material must be similar in both coloration and grain size distribution to that native beach. Beach compatible fill is material that maintains the general character and functionality of the material occurring on the beach and in the adjacent dune and coastal system. Fill material shall comply with FDEP requirements pursuant to the Florida Administrative Code (FAC) subsection 62B-41.005(15). A Quality Control Plan shall be implemented pursuant to FAC Rule 62B-41.008(1)(k)4.b.
- A3. Sand placement shall not occur during the period of peak sea turtle egg laying and egg hatching to reduce the possibility of sea turtle nest burial, crushing of eggs, or nest excavation.
- a. Sand placement projects in Brevard, Indian River, St. Lucie, Martin, Palm Beach, and Broward counties shall be started after October 31 and be completed before May 1. During the May 1 through October 31 period, no construction equipment or pipes may be placed and/or stored on the beach.
 - b. Sand placement projects in Nassau, Duval, St. Johns, Flagler, Volusia, Miami-Dade, Monroe, Collier, Lee, Charlotte, Sarasota, Manatee, Hillsborough, Pinellas, Franklin, Gulf, Bay, Walton, Okaloosa, Santa Rosa and Escambia Counties may occur during the sea turtle nesting season except on publicly owned conservation lands such as state parks and areas where such work is prohibited by the managing agency or under applicable local land use codes (see exceptions in A3.c below).
 - c. For higher density nesting beaches in Gulf and Franklin Counties and on Manasota Key located in Sarasota and Charlotte counties, sand placement shall not occur during the main part of the nesting season (June 1 through September 30). These beaches include St. Joseph Peninsula State Park, St. Joseph peninsula, and Cape San Blas in Gulf County, St. George Island in Franklin County, and Manasota Key in Sarasota and Charlotte counties.
- The Service shall be contacted for coordination, on a project-by-project basis, if sand placement is needed on publicly owned conservation lands and in these higher density nesting beaches in Gulf and Franklin Counties and on Manasota Key in Sarasota and Charlotte counties during the above exclusionary period. The Service will determine whether work (1) may proceed in accordance with the Terms and Conditions; (2) proceed in accordance with the Terms and Conditions and other requirements as developed by the Service; or (3) would require that an individual emergency consultation be conducted.
- A4. All derelict concrete, metal, and coastal armoring geotextile material and other debris shall be removed from the beach prior to any sand placement to the maximum extent possible. If debris removal activities take place during the peak sea turtle nesting season (**Tables 17 and 18**), the work shall be conducted during daylight hours only and shall not commence until completion of the sea turtle nesting survey each day.

Table 15. Beach Sand Placement and Sea Turtle Nest Monitoring/Relocation Windows, Brevard through Broward Counties, Coast of Florida.

| Region | Nest Laying Season | Hatching Season Ends | Beach Placement Window | Early Season Relocation * | Late Season Relocation* * | Nesting Season Monitoring |
|--|---------------------------|-----------------------------|-------------------------------|---|--|----------------------------------|
| Brevard, Indian River, St. Lucie, and Broward Counties | 25 Feb - 11 Nov | 15 Jan | 1 Nov - 30 Apr | 1 Mar - 30 Apr In St. Lucie County, nighttime surveys for leatherback sea turtles shall begin when the first leatherback crawl is recorded | 65 days prior to 1 Nov (28 Aug) (or prior to start of construction **) | 1 Mar - 15 Oct |
| Martin and Palm Beach Counties | 12 Feb - 16 Oct | 20 Dec | 1 Nov - 30 Apr | 1 Mar - 30 Apr In Martin and Palm Beach Counties, nighttime surveys for leatherback sea turtles shall begin when the first leatherback crawl is recorded | 65 days prior to 1 Nov (28 Aug) (or prior to start of construction **) | 1 Mar - 15 Oct |

Table 16. Beach Sand Placement and Sea Turtle Nest Monitoring/Relocation Windows, Outside of Brevard through Broward Counties, Coast of Florida.

| Region | Nest Laying Season | Hatching Season Ends | Beach Placement Window | Nesting Season Monitoring and Relocation |
|--|---------------------------|-----------------------------|-------------------------------|---|
| Nassau, Duval, St. Johns, Flagler, and Volusia Counties | 27 Apr - 3 Oct | 30 Nov | All Year | 15 Apr – 30 Sep |
| Miami-Dade County | 30 Mar - 25 Sep | 30 Nov | All Year | 1 Apr – 30 Sep |
| Gulf County (St. Joseph Peninsula State Park, St. Joseph peninsula, Cape San Blas) and Franklin County (St. George Island) | 1 May - 4 Sep | 15 Nov | 1 Oct - 31 May | 1 May – 15 Sep |
| All other beaches in Gulf and Franklin Counties, and Escambia, Santa Rosa, Okaloosa, Walton, and Bay Counties | 11 May - 5 Sep | 15 Nov | All Year | 1 May - 31 Aug |
| Sarasota and Charlotte Counties (Manasota Key) | 27 Apr - 7 Sep | 15 Nov | 1 Nov - 30 Apr | 15 Apr – 15 Sep |
| All other beaches in Sarasota and Charlotte Counties | 27 Apr - 7 Sep | 15 Nov | All Year | 15 Apr – 15 Sep |
| Pinellas, Hillsborough, Manatee, Lee, Collier, and Monroe Counties | 24 Apr - 11 Sep | 15 Nov | All Year | 15 Apr – 15 Sep |

- A5. The Corps shall continue to work with FDEP, FWC and the Service in conducting the second phase of testing on the sea turtle friendly profile during project construction. This includes exploring options to include a dune system in the project design for existing authorized projects and new non-Federal projects and how the existing sand placement template may be modified.

A6. Dune restoration or creation included in the profile design (or project) shall have a slope of 1.5:1 followed by a gradual slope of 4:1 for approximately 20 feet seaward on a high erosion beach (**Figure 13**) or a 4:1 slope (**Figure 14**) on a low erosion beach. If another slope is proposed for use, the Corps shall consult the Service.




Figure 13. Recommended slope on a high erosion beach for sand placement projects that include the creation of a dune.




Figure 14. Recommended slope on a low erosion beach for sand placement projects that include the creation of a dune.

- A7. Predator-proof trash receptacles shall be installed and maintained during construction at all beach access points used for the project construction to minimize the potential for attracting predators of sea turtles and beach mice (**Appendix C**). The Corps shall provide predator-proof trash receptacles for the construction workers. The Corps shall brief workers on the importance of not littering and keeping the project area trash and debris free.
- A8. A meeting between representatives of the Corps, the Service, the FWC, the permitted sea turtle surveyor, and other species surveyors, as appropriate, shall be held prior to the commencement of work on projects. At least 10 business days advance notice shall be provided prior to conducting this meeting. The meeting will provide an opportunity for explanation and/or clarification of the sea turtle and beach mouse protection measures as well as additional guidelines when construction occurs during the sea turtle nesting season, such as storing equipment, minimizing driving, free-roaming cat observation, and reporting within the work area, as well as follow up meetings during construction (**Table 3**).

Sea Turtle Protection

- A9. Daily early morning surveys for sea turtle nests shall be required as outlined in **Tables 15 and 16 (Nesting Season Monitoring)**. If nests are constructed in the area of sand placement, the eggs shall be relocated to minimize sea turtle nest burial, crushing of eggs, or nest excavation as outlined in a through f.
 - a. For sand placement projects in Brevard, Indian River, St. Lucie, Martin, Palm Beach, and Broward Counties that occur during March 1 through April 30, daily early morning surveys and egg relocation shall be conducted for sea turtle nests until completion of the project (whichever is earliest). Eggs shall be relocated per the following requirements. For sand placement projects that occur during the period from November 1 through November 30, daily early morning sea turtle nesting surveys shall be conducted 65 days prior to project initiation and continue through November 30, and eggs shall be relocated per the requirements listed in (a)i through (a)iii.
 - i. Nesting surveys and egg relocations will only be conducted by persons with prior experience and training in these activities and who are duly authorized to conduct such activities through a valid permit issued by FWC, pursuant to FAC 68E-1. Please contact FWC's Imperiled Species Management Section in Tequesta at (561) 575-5407 for information on the permit holder in the project area. Nesting surveys shall be conducted daily between sunrise and 9 a.m. (this is for all time zones).
 - ii. Only those nests that may be affected by sand placement activities will be relocated. Nest relocation shall not occur upon completion of the project. Nests requiring relocation shall be moved no later than 9 a.m. the morning following deposition to a nearby self-release beach site in a secure setting where artificial lighting will not interfere with hatchling orientation. Relocated nests shall not

be placed in organized groupings. Relocated nests shall be randomly staggered along the length and width of the beach in settings that are not expected to experience daily inundation by high tides or known to routinely experience severe erosion and egg loss, predation, or subject to artificial lighting. Nest relocations in association with construction activities shall cease when construction activities no longer threaten nests.

- iii. Nests deposited within areas where construction activities have ceased or will not occur for 65 days or nests laid in the nourished berm prior to tilling shall be marked and left in situ unless other factors threaten the success of the nest. The turtle permit holder shall install an on-beach marker at the nest site and a secondary marker at a point as far landward as possible to assure that future location of the nest will be possible should the on-beach marker be lost. No activity will occur within this area nor will any activities occur that could result in impacts to the nest. Nest sites shall be inspected daily to assure nest markers remain in place and the nest has not been disturbed by the project activity.

During the period from March 1 through April 30, daytime surveys shall be conducted for leatherback sea turtle nests beginning March 1. Nighttime surveys for leatherback sea turtles shall begin when the first leatherback crawl is recorded within the project or adjacent beach area through April 30 or until completion of the project (whichever is earliest). Nightly nesting surveys shall be conducted from 9 p.m. until 6 a.m. The project area shall be surveyed at 1-hour intervals (since leatherbacks require at least 1.5 hours to complete nesting, this will ensure all nesting leatherbacks are encountered) and eggs shall be relocated per the requirements listed in (a)i through (a)iii.

- b. For sand placement projects in Nassau, Duval, St. Johns, Flagler, Volusia, Miami-Dade, Monroe, Collier, Lee, Charlotte, Sarasota, Manatee, Hillsborough, Pinellas, Franklin, Gulf, Bay, Walton, Okaloosa, Santa Rosa and Escambia Counties that occur during the period from May 1 through October 31, daily early morning (before 9 a.m.) surveys and egg relocation shall be conducted. If nests are laid in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii (see nest relocation exceptions for Franklin, Gulf, Sarasota, and Charlotte Counties in A9.d. below).
- c. For Franklin, Gulf, Bay, Walton, Okaloosa, Santa Rosa, and Escambia Counties, nesting surveys shall be initiated 70 days prior to sand placement activities (incubation periods are longer in these counties) or by May 1 whichever is later. Nesting surveys and relocation shall continue through the end of the project or through August 31 whichever is earlier. Hatching and emerging success monitoring will involve checking nests beyond the completion date of the daily early morning nesting surveys. If nests are laid in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii (see nest relocation exceptions for Franklin and Gulf Counties in A9.d. below).

- d. For St. Joseph Peninsula State Park, St. Joseph peninsula, and Cape San Blas in Gulf County, St. George Island in Franklin County, and Manasota Key in Sarasota and Charlotte Counties, sand placement activities shall not occur from June 1 through September 30, the period of peak sea turtle egg laying and egg hatching for this area. If nests are laid between May 1 and May 31 in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii.
 - e. For Pinellas, Hillsborough, Manatee, Sarasota, Charlotte, Lee, Collier, and Monroe Counties, nesting surveys shall be initiated 65 days prior to nourishment or dredged channel material placement activities or by April 15 whichever is later. Nesting surveys and egg relocation shall continue through the end of the project or through September 30 whichever is earlier. If nests are laid in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii (see nest relocation exceptions for Sarasota and Charlotte Counties in A9.d. above).
 - f. For Miami-Dade County, nesting surveys shall be initiated 65 days prior to nourishment or dredged channel material placement activities or by April 1 whichever is later. Nesting surveys and egg relocation shall continue through the end of the project or through September 30 whichever is earlier. If nests are laid in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii
 - g. For Volusia, Flagler, St. Johns, Duval, and Nassau Counties, nesting surveys shall be initiated 65 days prior to sand placement activities or by April 15 whichever is later. Nesting surveys and egg relocation shall continue through the end of the project or through September 30 whichever is earlier. If nests are laid in areas where they may be affected by construction activities, eggs shall be relocated per the requirements listed in (a)i through (a)iii.
- A10. Daily nesting surveys shall be conducted for two nesting seasons in accordance with the FWC's Statewide Nesting Beach Survey Protocol (**Appendix B**) by the Corps or the Applicant following construction if placed material still remains on the beach (**Table 17**). Post construction year-one surveys shall record the number of nests, nesting success, reproductive success, and lost nests due to erosion and/or inundation. Post construction year-two surveys shall only need to record nest numbers and nesting success. This information will be used to periodically assess the cumulative effects of these projects on sea turtle nesting and hatchling production and monitor suitability of post construction beaches for nesting.

Table 17. Post-Construction Sea Turtle Monitoring.

| Region | Nest Laying Season | Years 1 and 2 Post-Construction Monitoring |
|--|---------------------------|--|
| Brevard, Indian River, St. Lucie, and Broward Counties | 25 Feb - 11 Nov | Bi-weekly surveys: 1 Mar - 30 Apr and from 15 Oct – 15 Nov Daily surveys: 1 May - 15 Oct |
| Martin and Palm Beach Counties | 12 Feb - 16 Oct | Daily surveys: 1 Mar - 15 Oct |
| Nassau, Duval, St. Johns, Flagler, and Volusia Counties | 27 Apr - 3 Oct | Daily surveys: 1 May – 30 Sep |
| Miami-Dade County | 30 Mar - 25 Sep | Daily surveys: 1 Apr – 30 Sep |
| Gulf County (St. Joseph Peninsula State Park, St. Joseph peninsula, Cape San Blas) and Franklin County (St. George Island) | 1 May - 4 Sep | Daily surveys: 1 May – 31 Aug |
| All other beaches in Gulf and Franklin Counties, and Escambia, Santa Rosa, Okaloosa, Walton, and Bay Counties | 11 May - 5 Sep | Daily surveys: 1 May - 31 Aug |
| Sarasota and Charlotte Counties (Manasota Key) | 27 Apr - 7 Sep | Daily surveys: 1 May –15 Sep |
| All other beaches in Sarasota and Charlotte Counties | 27 Apr - 7 Sep | Daily surveys: 1 May – 15 Sep |
| Pinellas, Hillsborough, Manatee, Lee, Collier, and Monroe Counties | 24 Apr - 11 Sep | Daily surveys: 1 May – 15 Sep |

- A11. Two surveys shall be conducted of all lighting visible from the beach placement area by the Applicant or Corps, using standard techniques for such a survey (**Appendix C**), in the year following construction. The first survey shall be conducted between May 1 and May 15 and a brief summary provided to the Service. The second survey shall be conducted between July 15 and August 1. A summary report of the surveys, including any actions taken, shall be submitted to the Service by December 1 of the year in which surveys are

conducted. After the annual report is completed, a meeting shall be set up with the Applicant, county or municipality, FWC, Corps, and the Service to discuss the survey report, as well as any documented sea turtle disorientations in or adjacent to the project area. If the project is completed during the nesting season and prior to May 1, the Corps may conduct the lighting surveys during the year of construction.

- A12. Sand compaction shall be monitored in the area of sand placement immediately after completion of the project and prior to the dates in **Table 18** for 3 subsequent years.

Table 18. Dates for Compaction Monitoring and Escarpment Surveys by County.

| County where project occurs | Date |
|---|-------------|
| Brevard, Indian River, St. Lucie, Martin, Palm Beach, and Broward | March 1 |
| Escambia, Santa Rosa, Okaloosa, Walton, Bay, Gulf, Franklin, Volusia, Flagler, St. Johns, Duval, Nassau, Pinellas, Hillsborough, Manatee, Sarasota, Charlotte, Lee, Collier | April 15 |
| Miami-Dade, Monroe | April 1 |

If tilling is needed, the area shall be tilled to a depth of 36 inches. Each pass of the tilling equipment shall be overlapped to allow more thorough and even tilling. All tilling activity shall be completed at least once prior to the nesting season. An electronic copy of the results of the compaction monitoring shall be submitted to the appropriate Service Field Office (**Table 3**) prior to any tilling actions being taken or if a request not to till is made based on compaction results. The requirement for compaction monitoring can be eliminated if the decision is made to till regardless of post construction compaction levels. Additionally, out-year compaction monitoring and remediation are not required if placed material no longer remains on the dry beach.

(NOTE: If tilling occurs during shorebird nesting season (February 15-August 31), shorebirds surveys prior to tilling are required per the Migratory Bird Treaty Act http://myfwc.com/docs/Conservation/FBCI_BNB_SeaTurtleMonitors.pdf)

- a. Compaction sampling stations shall be located at 500-foot intervals along the sand placement template. One station shall be at the seaward edge of the dune/bulkhead line (when material is placed in this area), and one station shall be midway between the dune line and the high water line (normal wrack line).
- b. At each station, the cone penetrometer shall be pushed to a depth of 6, 12, and 18 inches three times (three replicates). Material may be removed from the hole if necessary to ensure accurate readings of successive levels of sediment. The penetrometer may need to be reset between pushes, especially if sediment layering exists. Layers of highly compact material may lie over less compact layers. Replicates shall be located as close to each other as possible, without interacting with the previous hole or disturbed sediments. The three replicate compaction values for each depth shall be averaged to produce final values for each depth at

each station. Reports will include all 18 values for each transect line, and the final six averaged compaction values.

- c. If the average value for any depth exceeds 500 pounds per square inch (psi) for any two or more adjacent stations, then that area shall be tilled immediately prior to the appropriate date listed in **Table 18**.
- d. If values exceeding 500 psi are distributed throughout the project area but in no case do those values exist at two adjacent stations at the same depth, then consultation with the Service will be required to determine if tilling is required. If a few values exceeding 500 psi are present randomly within the project area, tilling will not be required.
- e. Tilling shall occur landward of the wrack line and avoid all vegetated areas 3 square feet or greater with a 3 square foot buffer around the vegetated areas.

- A13. Visual surveys for escarpments along the project area shall be made immediately after completion of the sand placement and within 30 days prior to the start dates for Nesting Season Monitoring in **Tables 15 and 16** for 3 subsequent years if sand in the project area still remains on the dry beach.

Escarpments that interfere with sea turtle nesting or that exceed 18 inches in height for a distance of 100 feet shall be leveled and the beach profile shall be reconfigured to minimize scarp formation by the dates listed above. Any escarpment removal shall be reported by location. If the project is completed during the early part of the sea turtle nesting and hatching season (March 1 through April 30), escarpments may be required to be leveled immediately, while protecting nests that have been relocated or left in place. The Service shall be contacted immediately if subsequent reformation of escarpments that interfere with sea turtle nesting or that exceed 18 inches in height for a distance of 100 feet occurs during the nesting and hatching season to determine the appropriate action to be taken. If it is determined that escarpment leveling is required during the nesting or hatching season, the Service or FWC will provide a brief written authorization within 30 days that describes methods to be used to reduce the likelihood of impacting existing nests. An annual summary of escarpment surveys and actions taken shall be submitted to the appropriate Service Field Office (**Table 3**).

- A14. If available, staging areas for construction equipment shall be located off the beach during early (March 1 through April 30) and late (November 1 through November 30) nesting season for Brevard through Broward counties and peak nesting season (May 1 through October 31) for the remaining counties. Nighttime storage of construction equipment not in use shall be off the beach to minimize disturbance to sea turtle nesting and hatching activities. In addition, all construction pipes placed on the beach shall be located as far landward as possible without compromising the integrity of the dune system. Pipes placed parallel to the dune shall be 5 to 10 feet away from the toe of the dune if the width of the beach allows. Temporary storage of pipes shall be off the beach to the maximum extent possible. If the pipes are stored on the beach, they shall be placed in a manner that will minimize the impact to nesting habitat and shall not compromise the integrity of the dune systems.

- A15. Direct lighting of the beach and nearshore waters shall be limited to the immediate construction area during early (March 1 through April 30) and late (November 1 through November 30) nesting season for Brevard through Broward counties and peak nesting season (May 1 through October 31) for the remaining counties, and shall comply with safety requirements. Lighting on all equipment shall be minimized through reduction, shielding, lowering, and appropriate placement to avoid excessive illumination of the water's surface and nesting beach while meeting all Coast Guard, Corps EM 385-1-1, and OSHA requirements. Light intensity of lighting equipment shall be reduced to the minimum standard required by OSHA for General Construction areas, in order not to misdirect sea turtles. Shields shall be affixed to the light housing and be large enough to block light from all lamps from being transmitted outside the construction area or to the adjacent sea turtle nesting beach in line-of-sight of the dredge (**Figure 15**).




Figure 15. Beach lighting schematic.

- A16. During the period during early (March 1 through April 30) and late (November 1 through November 30) nesting season for Brevard through Broward counties and peak nesting season (May 1 through October 31) for the remaining counties, the Corps shall not extend the beach fill more than 500 feet (or other agreed upon length) along the shoreline between dusk and dawn of the following day until the daily nesting survey has been completed and the beach cleared for fill advancement. An exception to this may occur if there is a permitted sea turtle surveyor present on-site to ensure no nesting and hatching sea turtles are present within the extended work area. If the 500 feet is not feasible for the project, an agreed upon distance will be decided on during the preconstruction meeting. Once the beach has been cleared and the necessary nest relocations have been completed, the Corps will be allowed to proceed with the placement of fill during daylight hours until dusk at which time the 500-foot length (or other agreed upon length) limitation shall apply. If any

nesting turtles are sighted on the beach within the immediate construction area, activities shall cease immediately until the turtle has returned to the water and the sea turtle permit holder responsible for nest monitoring has relocated the nest.

Dune Planting

- A17. All vegetation planting shall be designed and conducted to minimize impacts to sea turtles and beach mice. Dune vegetation planting may occur during the sea turtle nesting season under the following conditions.
- a. Daily early morning sea turtle nesting surveys (before 9 a.m.) shall be conducted during the period from May 1 through October 31 for all counties in Florida where sea turtle nesting occurs. If the planting is conducted in Brevard, Indian River, St. Lucie, Martin, Palm Beach, or Broward Counties, daily early morning surveys shall be extended to include March 1 through April 30 and November 1 through November 30. Nesting surveys shall only be conducted by personnel with prior experience and training in nesting surveys. Surveyors shall have a valid FWC permit. Nesting surveys shall be conducted daily between sunrise and 9 a.m. (all times). No dune planting activity shall occur until after the daily turtle survey and nest conservation and protection efforts have been completed. Hatching and emerging success monitoring will involve checking nests beyond the completion date of the daily early morning nesting surveys;
 - b. Any nests deposited in the dune planting area not requiring relocation for conservation purposes shall be left in place. The turtle permit holder shall install an on-beach marker at the nest site and a secondary marker at a point as far landward as possible to assure that future location of the nest will be possible should the on-beach marker be lost. A series of stakes and highly visible survey ribbon or string shall be installed to establish a 3-foot radius around the nest. No planting or other activity shall occur within this area nor will any activities be allowed that could result in impacts to the nest. Nest sites shall be inspected daily to assure nest markers remain in place and the nest has not been disturbed by the planting activity;
 - c. If a nest is disturbed or uncovered during planting activity, the Corps, or the Applicant shall cease all work and immediately contact the project turtle permit holder. If a nest(s) cannot be safely avoided during planting, all activity within 10 feet of a nest shall be delayed until hatching and emerging success monitoring of the nest is completed;
 - d. All dune planting activities shall be conducted by hand and only during daylight hours;
 - e. All dune vegetation shall consist of coastal dune species native to the local area; (*i.e.*, native to coastal dunes in the respective county and grown from plant stock from that region of Florida). Vegetation shall be planted with an appropriate amount of fertilizer and antidesiccant material for the plant size;

- f. No use of heavy equipment shall occur on the dunes or seaward for planting purposes. A lightweight (all-terrain type) vehicle, with tire pressures of 10 psi or less may be used for this purpose; and
- g. Irrigation equipment, if needed, shall be authorized under a FDEP permit.

Beach Mouse Protection

- A18. Beach mouse habitat shall be avoided when selecting sites for equipment, pipes, vehicle storage and staging to the maximum extent possible. Suitable beach mouse habitat constitutes the primary dunes (characterized by sea oats and other grasses), secondary dunes (similar to primary dunes, but also frequently includes such plants as woody goldenrod, false rosemary), and interior or scrub dunes.
- A19. Equipment placement or storage shall be excluded in the area between 5 to 10 feet seaward of the existing dune toe or 10 percent of the beach width (for projects occurring on narrow eroded beach segments) seaward of the dune toe in areas of occupied beach mouse habitat (**Figure 16**). The toe of the dune is where the slope breaks at the seaward foot of the dune.




Figure 16. Equipment placement for projects occurring in beach mouse occupied habitat.

- A20. Existing beach access points shall be used for vehicle and equipment beach access to the maximum extent possible. These access points shall be delineated by post and rope or other suitable material to ensure vehicles and equipment transport stay within the access corridor. The access corridors shall be fully restored to the preconstruction conditions following project completion. Parking areas for construction crews shall be located as close as possible to the work sites, but outside of vegetated dune areas to minimize impacts to existing habitat and transporting workers along the beachfront.