



ADDENDUM # 1

RFP # FY 2021-2022-010

CCNA ENGINEERING SERVICES FOR PARKWAY DR AND LESLIE DR

REVISED SCOPE

Please ensure you check the City's website for the latest addendum released for this project. Below find the link to the City's website: www.cohb.org/solicitations.

PLEASE NOTE: ORIGINAL SCOPE, PAGE 3

The intent of the project is to provide a new 16-inch and 12-inch potable water main system located in the City of Hallandale Beach, Florida. The proposed potable water main system will create a hydraulic loop along Parkview Drive from the intersection of Parkview Drive and Three Islands Boulevard to the north end of Parkview Drive and then west from Parkview Drive to the intersection of Three Island Boulevard and NE 11th Street. The new water main (transmission only) from the north end of Parkview Drive west to Three Island Boulevard will require coordination with the City of Hollywood for utility easements. The project will also include a new 12-inch water main on Leslie Drive from Parkview Drive south to where public Right-of-Way ends. The 12-inch water main on Leslie Drive will not be a looped system. The total length of the proposed water mains is approximately 5,300 feet. The City intends to replace the aging water main on Parkview Drive and establish a new hydraulic loop that does not currently exist to provide a more reliable and redundant potable water system. The project will include two (2) subaqueous water crossings that will be installed utilizing horizontal directional drill (HDD) so that the new water main will not be attached to the Parkview Drive bridge and to complete the hydraulic loop to the north. The existing water services and fire hydrants will be transitioned to the proposed water mains on Parkview Drive and Leslie Drive. Additional water services or fire hydrants are not anticipated on those roadways. New fire hydrants and water services are not proposed for the new section of water main (transmission only) from the north end of Parkview Drive west to Three Island Boulevard.

RFP # FY 2021-2022-010

CCNA ENGINEERING SERVICES FOR PARKWAY DR AND LESLIE DR

PLEASE NOTE: REVISED SCOPE, PAGE 3

The intent of the project is to provide a new 16-inch and 12-inch potable water main system located in the City of Hallandale Beach, Florida. The proposed potable 16-inch water main system will create a hydraulic loop along Parkview Drive from the intersection of Parkview Drive and Three Islands Boulevard to the north end of Parkview Drive and then west from Parkview Drive to the intersection of Three Island Boulevard and NE 11th Street. The new water main (transmission only) from the north end of Parkview Drive west to Three Island Boulevard will require coordination with the City of Hollywood for utility easements. The project will also include a new 12-inch water main on Leslie Drive from Parkview Drive south to where public Right-of-Way ends. The 12-inch water main on Leslie Drive will not be a looped system. The total length of the proposed water mains is approximately 5,300 feet. The City intends to replace the aging water main on Parkview Drive and establish a new hydraulic loop that does not currently exist to provide a more reliable and redundant potable water system. The project will include two (2) subaqueous water crossings that will be installed utilizing horizontal directional drill (HDD) so that the new water main will not be attached to the Parkview Drive bridge and to complete the hydraulic loop to the north. The existing water services and fire hydrants will be transitioned to the proposed water mains on Parkview Drive and Leslie Drive. Additional water services or fire hydrants are not anticipated on those roadways. New fire hydrants and water services are not proposed for the new section of water main (transmission only) from the north end of Parkview Drive west to Three Island Boulevard.

PLEASE NOTE RECEIPT OF ADDENDUM # 1 BY COMPLETING 'FORM P: ACKNOWLEDGEMENT OF ADDENDA' WITH YOUR FIRM'S SUBMISSION.